



15.009.02.007.0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 28 1966

CONSERVATION DIVISION
Wichita, Kansas

3-28-1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Chas. H. Keevert of Birmingham & Bartlett Drlg. has this date requested permission to plug the following described well:

Mr. E. L. Birmingham guarantees payment of the plugging fee.

Operator's full Name: Birmingham-Bartlett Drilling Company

Complete Address: 300 Kaufman Bldg., Wichita, Kansas

Lease Name: Alexian Well No. # 5

Location: C W/2 SW SE Sec. 36 Twp. 20 Rge. 12 (E)(W) W

County Barton Total Depth 3462 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Jim Beakie was instructed to plug the well as follows:

8 5/8" 256' Cwc.
Set bottom plug @ 3390' & dumped 5 sax cement with dump bailer. Pulled
pipe. Mud to 225'; set rock bridge; displaced 5 sax cement. Let set
over night. Bailed hole dry; displaced 20 sax cement. Mud to 40';
set rock bridge; displaced 10 sax cement, cementing to base of cellar.

Very truly yours,

Don L. ...
Conservation Division Agent