



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 18 1973

CONSERVATION DIVISION
Wichita, Kansas

6-18-1973

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Earl Baker of N. C. R. A. has this

date requested permission to plug the following described well:

Mr. Nat'l. Coop. Ref. Assoc guarantees payment of the plugging fee.

Operator's full Name: National Cooperative Refinery Association

Complete Address: Box # 6, Great Bend, Kansas 67530

Lease Name: McGreevy "B" Well No. # 4

Location: NE NW SE Sec. 33 Twp. 20 Rge. 14 (E) (W) W

County: Barton Total Depth 3627 Oil Well

Gas Well Input Well X SWD Well D & A Lost Hole

Mr. Albert Unruh was instructed to plug the well as follows:

8 5/8" csg. 836' Cwc. Perf. 3429'. Gas blow @ 1840'.

Sanded hole back to 3400' & dumped 5 sax cement with dump bailer.

Circulated hole with mud @ 1840' & displaced 100 sax cement @ 1625'

with Halliburton Cementing Company's pump truck. Pulled remaining pipe.

Mud to 450', set 25' rock bridge, & displaced 6 yds. Ready-mix Cement,

cementing from 425' to base of cellar.

Don Lruan
Conservation Division Agent