



15.009.00976.0000

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

FEB 21 1966

CONSERVATION DIVISION  
Wichita, Kansas

2-21-1966

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Dan Cook of Bovaird Supply Company has this date requested permission to plug the following described well:

Mr. R. W. Robbins guarantees payment of the plugging fee.

Operator's full Name: Bovaird Supply Company

Complete Address: 2808 10th St., Great Bend, Kansas

Lease Name: Byrant "A" Well No. # 1

Location: NW <sup>sw</sup> SE NE Sec. 27 Twp. 20 Rge. 12 (E)(W) W

County Barton Total Depth 3415 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Mike Wassinger was instructed to plug the well as follows:

8 5/8" 264' Cwc.

Set bottom plug @ 3150' & dumped 5 sax cement with dump bailer.

Pulled pipe. Mudded hole to 260'; set rock bridge: displaced 25 sax

cement. Mud to 40'; set rock bridge & displaced 10 sax cement,

cementing to base of cellar.

Very truly yours,

Don Truman  
Conservation Division Agent