

9-24

2-040573

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

API NUMBER: 15-159-20,785 <sup>.00 .00</sup> E-21,236

SE SW SW, SECTION 17 TOWNSHIP 18 RANGE 6W

OPERATOR LICENSE # 6141 330 FEET FROM S SECTION LINE  
4290 FEET FROM E SECTION LINE

OPERATOR R&B Petroleum, Inc.  
NAME & P. O. Box 1285  
ADDRESS Great Bend, KS 67530

LEASE NAME: Diffenbaugh #1  
COUNTY: Rice

WELL TOTAL DEPTH: 3387' <sup>110.07</sup>

CONDUCTOR PIPE: " @ '  
SURFACE CASING: 8-5/8" @ 221'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD  D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Kelso Casing Pulling  
ADDRESS: Chase, KS LICENSE: 6050

COMPANY TO PLUG AT: HOUR: 9:00a DAY: 19 MONTH: 9 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Jim  
COMPANY NAME: R&B Petroleum PHONE: \_\_\_\_\_

WERE: Sand to 2850' - c/w/4 sx - shoot off pipe - pull to  
1000' - spot 30 sx - pull to 630' & 30 sx - pull to  
275' & circ to surface.

PLUGGING PROPOSAL RECEIVED BY: \_\_\_\_\_

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART (  ) NONE (  )

COMPLETED: HOUR: 11:00a DAY: 24 MONTH: 9 YEAR: 1990

ACTUAL PLUGGING REPORT:  
Sanded to 2850' - c/w/4 sx - shot off pipe at 2350' -  
pulled to 1000' & spotted 30 sx - pulled to 630' &  
spotted 30 sx - pulled to 275' & circ to surf - 160 sx  
60/40 2% gel.

REMARKS: Allied #6023 cement circulated

I DID OBSERVE THIS PLUGGING.

INVOICED

RECEIVED  
CORPORATION COMMISSION

Ralph Tittel  
Ralph Tittel (AGENT)

DATE 10-8-90 0077 1990

INV. NO. 29558  
Wichita, Kansas

FORM CP-2/3  
REV. 3/90