

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

5-10

2-060254
RECEIVED
STATE CORPORATION COMMISSION
MAY 16 1991
CONSERVATION DIVISION
Wichita, Kansas
61
R
5-16-1991

API NUMBER: 15-159-21,025

SE NE SE, SECTION 25 TOWNSHIP 18 RANGE 7W

OPERATOR LICENSE # 6141

1650 FEET FROM S SECTION LINE
330 FEET FROM E SECTION LINE

OPERATOR R&B Petroleum, Inc.
NAME & Box 1285
ADDRESS Great Bend, KS 67530

LEASE NAME: Behnke "B" #1

COUNTY: Rice 108.87

WELL TOTAL DEPTH: 3350'

PIPE: 4-1/2" @ 3109'/150 sx

SURFACE CASING: 8-5/8" @ 234'

ABANDONED OIL WELL GAS WELL INPUT WELL SMD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Kelso Casing Pulling
ADDRESS: P. O. Box 347, Chase, KS 67524 LICENSE: 6050

COMPANY TO PLUG AT: HOUR: _____ am DAY: 10 MONTH: 5 YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Ron
COMPANY NAME: Kelso Casing Pulling PHONE: 316-938-2943

WERE: Sand to 2954' - cap w/4 sx cmt - shoot pipe - pull csq to 980' - 35 sx - pull csq to 630' - 35 sx cmt - pull csq to 300' - circ cmt to surface.

PLUGGING PROPOSAL RECEIVED BY: District #2

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 11:30a DAY: 10 MONTH: 5 YEAR: 1991

ACTUAL PLUGGING REPORT:
Sanded to 2954' - capped w/4 sx cmt - shot pipe & pulled csq to 989' - 35 sx cmt - pulled csq to 666' - 35 sx - pulled csq to 323' - circ 95 sx cmt to surf - recovered 2073' of 4-1/2" - perms 3004'-10'

REMARKS: B. J. Titan #635877 60/40 poz 2% gel

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 5-29-91
INV. NO. 31948

R. Phil Worley
R. Phil Worley (AGENT)

FORM CP-2/3
REV. 3/90

DW