

5 020288

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-159-22,023.00.00
50' E. OF
~~NE NW NE~~ SEC. 14, T. 18 S, R. 7 (W)E

1 4950 feet from N(S) section line

1600 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6141

Lease Name Behnke "C" Well # 2

Operator: R & B Petroleum, Inc.

County Rice 105.95

Name & Address 123 Main Street

Well Total Depth 3260 feet

White Plains, NY 10601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 3/8 feet 210'-130'SKS

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 342, Chase, Kansas 67524

Company to plug at: Hour: 1:30 PM Day: 15 Month: April Year: 1986

Plugging proposal received from Clay Duntz - Joe Maes

(company name) Kelso Casing Pulling (phone) 316 938 2457

were: Fill hole with sand to 3090' and cement with 4 sacks.

Bail hole to 400'. Set rock bridge From 400' to 385' and cement hole to base of cellar with 6 yards ready-mix concrete

Plugging Proposal Received by Alley J. Loman
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 PM Day: 15 Month: April Year: 1986

ACTUAL PLUGGING REPORT Hole filled with sand to 3090' and cemented with 4 sacks cement. Hole bailed to 400'. Rock bridge set From 400' to 385' and hole cemented to base of cellar with 6 yards ready-mix concrete

4 1/2" - 3258' - 125'SKS Per F 3138-40, 3184-88, 3198-3200

Remarks: 2480' of 4 1/2" casing recovered Tobias Birchworth Ticket # 3890
(If additional description is necessary, use BACK of this form.)

4-22-1986

INVOICED

DATE 4-23-86

APR 22 1986

Signed Alley J. Loman
(TECHNICIAN)

INV. NO. 13525

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: July 1, 1985
month day year

RECEIVED
KCC-KDHE
API Number 15- 159-22,023

OPERATOR: License # 6141
Name R & B Petroleum, Inc.
Address P. O. Box 1285
City/State/Zip Great Bend, Kansas 67530
Contact Person Lee Roy Legleiter
Phone 316-792-6702

NE NW NE
(Location) Sec 14 Twp 18 S, Rge 7 East West

Nearest lease or unit boundary line 330 feet.
County Rice
Lease Name Behnke 'C' Well# 2
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

JOINT OFFICE #5
Salina, KS
JUN 10 1985

CONTRACTOR: License # 5418
Name Allen Drilling Company
City/State Great Bend, Kansas 67530

Well Drilled For: Well Class: Type Equipment:
 Oil Swd Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Depth to Bottom of fresh water 72 feet
Lowest usable water formation Kiowa
Depth to Bottom of usable water 200 feet
Surface pipe by Alternate: 1 2
Surface pipe to be set 210 feet
Conductor pipe if any required feet
Ground surface elevation N.A. feet MSL

S.P. 6/30/85
1 8 5/8"
210

If OWWO: Old well info as follows:
Operator
Well Name
Comp Date Old Total Depth
Projected Total Depth 3400 feet
Projected Formation at TD Kinderhook
Expected Producing Formations N.A.

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.
6-6-85
Signature of Operator or Agent Robert D. Dougherty Title Geologist
Approved By 6-7-85 MHC/KDHE 6-7-85
This Authorization Expires 12-7-85
Form C-1 4/84

8891-55-H

APR 8 1985

APR 8 1985



GAMMA-GUARD SIDEWALL NEUTRON LOG

COMP. R. AND B. PETROLEUM INC. WELL BEHNKE C NO. 2 FIELD N.A. COUNTY RICE ST. KANSAS	COMPANY R. AND B. PETROLEUM INCORPORATED		
	WELL BEHNKE C NO. 2		
	FIELD N.A.		
	COUNTY RICE		STATE KANSAS
API NO. 15-159-22.023		OTHER SERVICES	
LOCATION 50' E. OF NE-NW-NE		CAL	
SEC. 14	TWP. 18S	RGE. 7W	
PERMANENT DATUM	GROUND LEVEL	ELEV. 1661	ELEV.: K.B. 1667
LOG MEASURED FROM	KELLY BUSHING 6	FT. ABOVE PERM. DATUM	D.F. N.A.
DRILLING MEASURED FROM	KELLY BUSHING		G.L. 1661
DATE	07/05/85	07/05/85	07/05/85
RUN NO.	GAMMA	NEUTRON	GUARD
DEPTH-DRILLER	3260	3260	3260
DEPTH-WELEX	3258	3258	3258
BTH. LOG INTER.	3230	3256	3244
TOP LOG INTER.	SURFACE	2260	CASING
CASING-DRILLER	8 5/8 @ 210		
CASING-WELEX	202		
BIT SIZE	7 7/8		
TYPE FLUID IN HOLE	STARCH		
DENS. VISC.	9.8 56		
PH FLUID LOSS	11.6 7.0 ML	ML	
SOURCE OF SAMPLE	FLOWLINE		
RM @ MEAS. TEMP.	.24 @ 94 F	@ F	
RHF @ MEAS. TEMP.	.23 @ 84 F	@ F	
RMC @ MEAS. TEMP.	.32 @ 84 F	@ F	
SOURCE RMF RMC	CALC. CALC.		
RM @ BHT	.21 @ 108 F	@ F	
TIME SINCE CIRC.	2 HOURS		
TIME ON BOTTOM	1:35 A.M.		
MAX. REC. TEMP.	108 F @ 3260	F @	F @
EQUIP. LOCATION	51088 GT. BEND		
RECORDED BY	M. JOHNSON		
WITNESSED BY	L. BOOKLESS		

FIELD
PRINT