

1-17

2-060236 169 R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-159-21,833 - 0000

NW NW NW, SECTION 9 TOWNSHIP 18 RANGE 7W

OPERATOR LICENSE # 8917 4950 FEET FROM S SECTION LINE
4950 FEET FROM E SECTION LINE

OPERATOR J. D. Production Co.
NAME & Box 309
ADDRESS Geneseo, KS 67444

LEASE NAME: Gray #1
COUNTY: Rice 105.59
WELL TOTAL DEPTH: 3249'

PIPE: 5-1/2" @ 3249'/100 SX
SURFACE CASING: 8-5/8" @ 260'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Nicholas Casing Pulling
ADDRESS: Box 108, Geneseo, KSD 67444 LICENSE: 6698

COMPANY TO PLUG AT: HOUR: _____ am DAY: 17 MONTH: 1 YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Allan Nicholas
COMPANY NAME: Nicholas Casing Pulling PHONE: _____

WERE: Sand up to 3096' - cap w/5 sx cmt - shoot pipe - pull pipe to 950' - 30 sx cmt - pull pipe to 700' - 30 sx cmt - pull pipe to 300' - 40 sx cmt - pull pipe to 80' - circ to surface.

PLUGGING PROPOSAL RECEIVED BY: District #2

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: noon DAY: 17 MONTH: 1 YEAR: 1991

ACTUAL PLUGGING REPORT:
Sanded to 3096' - capped w/5 sx cmt - shot pipe - pulled pipe to 960' - 30 sx cmt - pulled pipe to 680' - 30 sx cmt - pulled pipe to 280' - 40 sx cmt - pulled pipe to 80' - circ 20 sx cmt to surface - perfs 3144' - 51' - recovered 2100' of 5-1/2"

REMARKS: Ellsworth Redimix #15271 common slurry

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 2-11-91

INV. NO. 30675

R. Phil Worley
R. Phil Worley (AGENT)

RECEIVED
FEB 29 1991
CONSERVATION DIVISION
Wichita, Kansas
1-29-1991

FORM CP-2/3
REV. 3/90