

RECEIVED
STATE CORPORATION COMMISSION

2-060230

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

DEC 27 1990

CONSERVATION DIVISION
Wichita, Kansas

12-27-1990

API NUMBER: 15-159-21,978 ^{.00.00} D-23,959

NW , SECTION 9 TOWNSHIP 18 RANGE 7W

OPERATOR LICENSE # 8917 4950 FEET FROM S SECTION LINE
4290 FEET FROM E SECTION LINE

OPERATOR J. D. Production Co.
NAME & Box 309
ADDRESS Geneseo, KS 67444

LEASE NAME: Gray #2
COUNTY: Rice 110.89
WELL TOTAL DEPTH: 3412'
PIPE: 5-1/2" @ 3342'/150 sx

SURFACE CASING: 8-5/8" @ 276'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A
OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Nicholas Casing Pulling
ADDRESS: Box 108, Geneseo, KS 67444 LICENSE: 6698
COMPANY TO PLUG AT: HOUR: 8:30a DAY: 18 MONTH: 12 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Allen Nicholas
COMPANY NAME: Nicholas Casing Pulling PHONE: 316-824-6483

WERE: Sand to 3290' cap w/5 sx cmt - shoot pipe - pull csq to 950' - 30 sx cmt - pull csq to 700' - 30 sx cmt - pull csq to 326' - 40 sx cmt - pull csq to 80' - circ cmt to surface.

PLUGGING PROPOSAL RECEIVED BY: District #2

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 12:00p DAY: 18 MONTH: 12 YEAR: 1990

ACTUAL PLUGGING REPORT:
Sanded to 3290' - capped w/5 sx cmt - shot pipe - pulled pipe to 950' - 30 sx cmt - pulled pipe to 694' - 30 sx cmt - pulled pipe to 326' - 40 sx cmt - pulled pipe to 80' - 28 sx cmt - circ to surface - recovered 2500' of 5-1/2" - open hole.

REMARKS: Ellsworth Redi Mix #15245 - common slurry cement

I DID OBSERVE THIS PLUGGING.

R. Phil Worley
R. Phil Worley (AGENT)

FORM CP-2/3
REV. 3/90

INVOICED

DATE 1-9-91

INV. NO. 30430

pw

12-18