

6-18-90

15.159.00183.00.00
-060205

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER: Drilled 11/9/51
NE NE NE, SECTION 9 TOWNSHIP 18 RANGE 8W

OPERATOR LICENSE # 5097 4950 FEET FROM S SECTION LINE
330 FEET FROM E SECTION LINE

OPERATOR Martin Oil Producers, Inc.
NAME & 150 N. Main, #1010
ADDRESS Wichita, KS 67202

LEASE NAME: Shill #1

COUNTY: Rice

WELL TOTAL DEPTH: 3307'

CONDUCTOR PIPE: 5-1/2" @ 3305' -107.48

SURFACE CASING: 8-5/8" @ 216'

ABANDONED OIL WELL GAS WELL INPUT WELL SHD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Nicholas Casing Pulling

ADDRESS: Box 127, Lyons, KS 67554 LICENSE: 6698

COMPANY TO PLUG AT: HOUR: 9:00a DAY: 18 MONTH: 6 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Allen Nicholas

COMPANY NAME: Nicholas Casing Pulling PHONE: 316-824-6483

WERE: Sand to 3200' - cap w/5 sx cmt - shoot 5-1/2" @ 200' -
pull pipe to 1100' & 50 sx - pull to 700' & 35 sx -
pull to 265' & circ cmt to surface.

PLUGGING PROPOSAL RECEIVED BY: Ralph Tittel

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { } PART { } NONE { }

COMPLETED: HOUR: 12:30p DAY: 18 MONTH: 6 YEAR: 1990

ACTUAL PLUGGING REPORT:

Sanded to 3200' & capped w/5 sx - tried to shoot @
2000' - 5-1/2" pulled apart @ 735' - pumped 40 sx cmt -
pulled pipe to 350' & 35 sx cmt - pulled to 150' &
circ 47 sx cmt to surface.

REMARKS: Ferfs 3277-81'; 3268-72' - Mid-America Redimix #8982
cement slurry.

I DID OBSERVE THIS PLUGGING.

INVOICED RECEIVED
STATE CORPORATION COMMISSION

Phil Worley
Phil Worley (AGENT)

DATE 7-17-90 JUL 9 1990 7-9-1990
INV. NO. 28600

FORM CP-2/3
REV. 3/90

CONSERVATION DIVISION
Wichita, Kansas

MK