

5 020241

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-159-21,657.00.00

SW NE NW SEC. 13, T. 19 S., R. 8 (W) (D)

4920 feet from N(S) section line

3630 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5035

Lease Name LeClere Well # 1-C

Operator: Aladdin Petroleum Corporation
Name & Address: 809 Petroleum Building
Wichita, Kansas 67202

County Rice

Well Total Depth ^{orig.} 3566 115 90 1260 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 252'-175 SKS

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, Kansas 67524

Company to plug at: Hour: 9:00 A Day: 17 Month: December Year: 1985

Plugging proposal received from Roger Lutz

(company name) Kelso Casing Pulling (phone) 316 938 2457

were: Fill hole with sand to 1175' and cement with 4 sacks cement.
Squeeze hole with 5 sacks Bentonite, 2 sacks hulls, and 100
sacks 60/40 Permox w/6% gel Pump into 8 5/8" surface casing.

Plugging Proposal Received by Alfred J. Lawson
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:20 A Day: 17 Month: December Year: 1985

ACTUAL PLUGGING REPORT Hole filled with sand to 1175' and cemented
with 4 sacks cement. Hole squeezed with 5 sacks Bentonite,
2 sacks hulls, and 100 sacks 60/40 Permox w/6% gel pumped into
8 5/8" surface casing.

4 1/2" - 1426-25 sacks Perfs 1224-42 Max Press. 300 PSIG. Close in Press. 100 PSIG.

Remarks: 1000' of 4 1/2" recovered, Allied Cementing Co. Inc. # 2091
(If additional description is necessary, use BACK of this form.)

I (did) (did not) observe this plugging:

STATE CORPORATION COMMISSION

Signed Alfred J. Lawson
(TECHNICIAN)

DEC 26 1985

CONSERVATION DIVISION

12-26-1985

FORM CP-2/3
Rev 101-84

INVOICED
DATE DEC 26 1985
1172L