

5 020242

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-159-20,567.00.00

CSW/NW, SEC. 13, T. 19 S, R. 8 (W) (B)

3300 feet from N(S) section line

4620 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5035

Lease Name Sanster Well # 1

Operator: Aladdin Petroleum Corporation
Name & Address: 809 Petroleum Bldg.
Wichita, Kansas 67202

County Rice
Well Total Depth 1430 46.48 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 7" feet 200-1005x

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, Kansas 67524

Company to plug at: Hour: 11:00 A Day: 17 Month: December Year: 1985

Plugging proposal received from Roger Lutz

(company name) Kelso Casing Pulling (phone) 316 938 2457

were: Fill hole with sand to 1190' and cement with 4 sacks cement.
Squeeze hole with 5 sacks Bentonite, 2 sacks hulls, and 100 sacks
60/40 Pozmix w/6% gel. Pump into 7" Surface casing.

Plugging Proposal Received by Stallard J. Loman
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 1:00 PM Day: 17 Month: December Year: 1985

ACTUAL PLUGGING REPORT Hole Filled with sand to 1190' and cemented with
5 sacks cement. Hole squeezed with 5 sacks Bentonite, 2
sacks hulls, and 75 sacks 60/40 Pozmix w/6% gel pumped into
7" Surface casing.

4 1/2" - 1429' - 75 sacks Perfs 1242-62 Max Pressure 400 PSIG. Hose in Press 200 PSIG

Remarks: 940' of 4 1/2" casing recovered Allied Cementing Co. Inc. Ticket # 2094
(If additional description is necessary, use BACK of this form.)

(did / did not) observe this plugging: _____

INVOICED

Signed Stallard J. Loman
(TECHNICIAN)

DATE DEC 26 1985

DEC 26 1985
12-26-1985
CONSERVATION DIVISION

INV. NO. 11722