

5-16

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER: 15-159-21,227.00.00

NE NE SE, SECTION 14 TOWNSHIP 19 RANGE 6W

OPERATOR LICENSE # 9132 2310 FEET FROM S SECTION LINE  
OPERATOR MILTON LACKEY 330 FEET FROM E SECTION LINE  
NAME & 382 FIRST AVENUE  
ADDRESS INMAN, KS 67546-8632  
LEASE NAME: SCHUBERT #1  
COUNTY: RICE  
WELL TOTAL DEPTH: 3490' 113.43  
PIPE: 3484' - 100SX  
SURFACE CASING: 8 5/8" @ 222'- 150 SX

ABANDONED OIL WELL X GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: QUALITY WELL SERVICE

ADDRESS: 249 EAST BETH DRIVE, STERLING, KS 67579 LICENSE: 31925

COMPANY TO PLUG AT: HOUR: PM DAY: 16 MONTH: 5 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: RICHARD McINTYRE

COMPANY NAME: QUALITY WELL SERVICE PHONE: (316) 727-3410

WERE: SAND TO 3338', CAP WITH 4 SACKS OF CEMENT. SHOOT PIPE. PULL CASING TO 950', LOAD HOLE, 35 SACKS OF CEMENT. PULL CASING TO 600', 35 SACKS OF CEMENT. PULL CASING TO 272', CIRCULATE CEMENT TO SURFACE.

PLUGGING PROPOSAL RECEIVED BY: DISTRICT II

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { X } PART { \_\_\_\_\_ } NONE { \_\_\_\_\_ }

COMPLETED: HOUR: 1:15PM DAY: 16 MONTH: 5 YEAR: 1997

ACTUAL PLUGGING REPORT: SANDED TO 3312', CAPPED WITH 4 SACKS OF CEMENT. SHOT PIPE. PULLED CASING TO 950', LOADED HOLE, 35 SACKS OF CEMENT. PULLED CASING TO 600', 35 SACKS OF CEMENT. PULLED CASING TO 272', CIRCULATED 140 SACKS OF CEMENT TO SURFACE.

RECOVERED 2834' PERFS: 3440'-42', 3424'-32', 3388'-92' 3447-49'

REMARKS: 60/40 POZ 4% GEL UNITED CEMENT #4296

RECEIVED  
KANSAS CORPORATION COMMISSION

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE JUN 06 1997

JUN 03 1997

Phil Worley  
PHIL WORLEY

'NV. NO. 48247

CONSERVATION DIVISION  
WICHITA, KS

6-3-1997