

4-28

2-100330

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-159-21,098.00.00

SE SE NE, SECTION 14 TOWNSHIP 19 RANGE 6W

OPERATOR LICENSE # 9132 2970 FEET FROM S SECTION LINE
OPERATOR MILTON LACKEY 330 FEET FROM E SECTION LINE
NAME & 382 FIRST AVENUE
ADDRESS INMAN, KS 67546

LEASE NAME: NELSON #1
COUNTY: RICE 112.78
WELL TOTAL DEPTH: 3470'
PIPE: 4 1/2" @ 3469'- 150 SX
SURFACE CASING: 8 5/8" @ 205'- 165 SX

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: QUALITY WELL SERVICE

ADDRESS: 249 EAST BETH DRIVE, STERLING, KS 67579 LICENSE: 31925

COMPANY TO PLUG AT: HOUR: AM DAY: 28 MONTH: 4 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: RICHARD McINTYRE

COMPANY NAME: QUALITY WELL SERVICE PHONE: (316) 727-3410

WERE: SAND TO 3362', CAP WITH 4 SACKS OF CEMENT. SHOOT PIPE. PULL CASING TO 950'; LOAD HOLE, 35 SACKS OF CEMENT. PULL CASING TO 600', 35 SACKS OF CEMENT. PULL CASING TO 255', CIRCULATE CEMENT TO SURFACE.

PLUGGING PROPOSAL RECEIVED BY: DISTRICT II

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { } PART { } NONE { }

COMPLETED: HOUR: 11:45AM DAY: 28 MONTH: 4 YEAR: 1997

ACTUAL PLUGGING REPORT: SANDED TO 3227', CAPPED WITH 4 SACKS OF CEMENT. SHOT PIPE. PULLED CASING TO 950'; LOADED HOLE, 35 SACKS OF CEMENT. PULLED CASING TO 600, 35 SACKS OF CEMENT. PULLED CASING TO 255', CIRCULATED 125 SACKS OF CEMENT TO SURFACE.

PERFS: 3412'-21', 3425'-27'

REC 2666'

REMARKS: 60/40 POZ 4% GEL UNITED CEMENT #4438

INVOICED

DATE MAY 05 1997

INV. NO. 48060

4-28

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 02 1997

I DID OBSERVE THIS PLUGGING.

Phil Worley
PHIL WORLEY

CONSERVATION DIVISION
WICHITA, KS

5-2-1997

FORM CP-2/3

REV. 3/90

20