

1 070250

Plugged 11-19-86 76

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097-21,224-0000 - R
150' West of
C NW NE, SEC. 32, T 30 S, R 18 W/E
4620 feet from S section line
2130 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5422

Lease Name Emerson Well # 1

Operator: Abercrombie Drilling, Inc.

County Kiowa 115.78

Name & Address 801 Union Center

Well Total Depth 5101 feet

Wichita, KS 67226

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 616

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67226

Company to plug at: Hour: 9:45 a.m. Day: 19 Month: 11 Year: 19 86

Plugging proposal received from Harold Maley

(company name) Abercrombie Drilling, Inc. (phone) 913-674-5768

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1097-1112'
Elevation 2163'

1st plug at 1150' with 50 sx cement, 2nd plug at 530' with 50 sx cement,

3rd plug at 40' with 10 sx cement, 4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 11:30 a.m. Day: 19 Month: 11 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1112' with 50 sx cement,

2nd plug at 635' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Reed
11-20-86

Remarks: Used 60/40 Pozmix 6% gel 3% cc by B.J. Titan.

(If additional description is necessary, use BACK of this form.)

INVOICED
(Do not) observe this plugging.

DATE 11-21-86

Signed Dan Goodrow
(TECHNICIAN)

INV. NO. 15393
11-19

(see rules on reverse side)

Starting Date 10 6 86
month day year

API Number 15-097-21,224
150' west of
C NW NE Sec. 32 Twp. 30 S, Rg. 18
4620 Ft. from South Line of Section
2130 Ft. from East Line of Section

OPERATOR: License # 5422
Name Abercrombie Drilling, Inc.
Address 801 Union Center
City/State/Zip Wichita, Kansas 67226
Contact Person Jack L. Partridge
Phone 316-262-1841

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 510 feet
County Kiowa

CONTRACTOR: License # 5422
Name Abercrombie Drilling, Inc.
City/State Wichita, Kansas

Lease Name Emerson Well # 1
Ground surface elevation est. 2160 feet MSL

Well Drilled For: Well Class: Type Equipment:
X Oil SWD Infield X Mud Rotary
X Gas Inj X Pool Ext. Air Rotary
OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no

Depth to bottom of fresh water 200
Depth to bottom of usable water 225 245

Surface pipe by Alternate: 1 X
Surface pipe planned to be set 500

Conductor pipe required
Projected Total Depth 5000 feet

Formation Mississippian

If OWWO: old well info as follows:

Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 10-2-86 Signature of Operator or Agent Title Vice-President

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 260 feet per Alt. X

This Authorization Expires 4-3-87 Approved By R.H. 10-3-86

SP rd 10-10-86

500' of 8 5/8" Drilled out cement on string
If lost circ. will set 1000
10-24-86 set surf. pulled
11-8-86 NO

Will call back for plugging orders

10-20-86

SP set @ 603'

100sx on bottom - 1140sx to cement top

10-18-86 150' West of C NW NE Sec. 32 Twp. 30 S, Rg. 18 X West
Bad lost Circ problem - SP stuck @ 250 - washed it back
out & reamed to 6 1/2"

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 1150 feet depth with 50 sxs of 60-40 posmix
2nd plug @ 500 530 feet depth with 50 sxs of 60-40 posmix
3rd plug @ Top 40' feet depth with 10 sxs of 60-40 posmix
4th plug @ feet depth with sxs of
5th plug @ feet depth with sxs of
(2) Rathole with 15 sxs (h) Mousehole with 10 sxs

316-723-2111

Harold Masley
PUSHER Wayne Schively
TD 5101' FORMATION M155.
SURFACE PIPE 8 5/8" @ 616'
ANHYDRITE 1097-1112' ELEVATION 2163'
STARTING TIME & DATE 9:45 am 11-19
COMPLETION TIME & DATE 11:30 AM
1st PLUG @ Base of Any FT. W/ 50 SXS
2nd PLUG @ 635' FT. W/ 50 SXS
3rd PLUG @ 40 FT. W/ 10 SXS
4th PLUG @ FT. W/ SXS
60-40 PR. 59991 Sec. 15 SXS
RAT HOLE CIRCULATED W/ 15 SXS
MOUSE HOLE CIRCULATED W/ 10 SXS
WATER WELL PLUGGED W/ SXS
CEMENT COMPANY B.J. Tilton
TECHNICIAN

NOV 11 1986