

To: 6 062465  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-009.02005.0000 212 R

SE, SEC. 36, T 20 S, R 12 (W)E  
990 feet from S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229

Lease Name Alexian Well # A-2

Operator: Phillips Petroleum Company  
Name &  
Address Rt. 3 Box 20-A  
Great Bend, Kansas 67530

County Barton 110.92  
Well Total Depth 3413' feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 250'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, Kansas 67524

Company to plug at: Hour: 11:00A.M. Day: 5 Month: August Year: 19 91

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: Order 250 sk. of 60/40 posmix - 8% gel. - 5 sks. hulls.

Plugging Proposal Received by Gilbert G. Scheck  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:00P.M. Day: 5 Month: July Year: 19 91

ACTUAL PLUGGING REPORT 8 5/8" set at 250' w/200 sks. 5 1/2" set at 3389' w/125 sks.

Top perf. at 3389'. Plugged bottom with sand and 5 sks. cement to 3325'.

Shot pipe 3 times and recovered 1300'. Pumped in 5 1/2" casing and circulated cement from 800' to surface. Pulled all casing and squeezed to 600 P.S.I. Used 250 sks. cement.

RECEIVED  
STATE CORPORATION COMMISSION  
8-21-1991

Remarks: By Allied Ran Line to 3000'. AUG 21 1991

(If additional description is necessary, use BACK of this form.)

INVOICED  
~~XXXXXX~~ observe this plugging.

DATE 9-5-91

WV. NO. 32950

Signed Gilbert G. Scheck  
(TECHNICIAN) E.A.S.