

6 060298

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-009.00730.0000

SW, SEC. 36, T. 20 S., R. 12 W. 1/4

330 feet from NS section line

330 feet from W1/4 section line

DANNEBOHN
Lease Name Jannabahn Well # 1

County Barton

Well Total Depth 3435 111.64 feet

Conductor-Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 2505

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238

Operator: Petroleum, Inc.

Name & Address Box 1447,

Great Bend, Ks.

67530

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering License Number 5111

Address Box 698, Great Bend, Ks. 67530

Company to plug at: Hour: 9:30AM Day: 25 Month: July Year: 1984

Plugging proposal received from D.B. Public

(company name) Rockhold Engineering (phone) _____

were: Order 16 5 sh. 50 pos mix - 60 lbs. 3% cel., 15 sh. July, 5 sh. hulls & 8 5/8" plug.

RECEIVED

STATE CORPORATION COMMISSION

JUL 30 1984 7-30-1984

Plugging Proposal Received by [Signature] (TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:15PM Day: 25 Month: July Year: 1984

ACTUAL PLUGGING REPORT 8 5/8" set at 250' w/ 225 sh. 4 1/2" set at 3433' w/ 75 sh.

Top perf at 3389', Plugged bottom w/ 4 sh cement, sand & 4 sh cement to 3260'. Shot pipe 4 times & recovered 338'. Pumped in 8 5/8" - 4 sh. hulls, 25 sh. cement, 12 sh. cel., 40 sh. cement, 3 sh. cel., 1 sh. hulls, released plug & followed w/ 100 sh cement w/ 850 pounds pressure

Remarks: By Allied

(If additional description is necessary, use BACK of this form.)

INVOICED

(old / did not) observe this plugging.

DATE 8-1-84

Signed [Signature] (TECHNICIAN)

INV. NO. 2816