

4-071116

8-25

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-009-21,652-0000

NE SE SE /4 SEC. 33, 20 S, 14 W
990 feet from S section line
330 feet from E section line

Operator license# 5363 Lease McGreevy B well # 10

Operator: Berexco, Inc. County Barton

Address: P.O. Box 723 Well total depth 3554 feet ^{115.51}
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet
Ted Crawford Surface pipe 8 5/8 Inch @ 815 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing - Kelso Casing License# -

Address: Great Bend, Kansas 67530 - Chase, Kansas 67524

Company to plug at: Hour: P.M. Day: 25 Month: August Year: 94

Plugging proposal received from: Manny - Ted Crawford

Company: Kelso Casing - Berexco, Inc. Phone: 913-628-6101

Were: 8 5/8" - 815' S.P. cwc. w/425 sxs. cement. 5 1/2" casing set at 3550' w/100 sxs. cement. Elv. 1912' - Anhy. 800' - Casing good. Perfs. open hole 3550' - 3554'. At bottom sand to 3500' and with 5 sxs. cement. Shot casing at 2718' - recovered 2718'. Proposal 250 sxs. 60/40 pozmix - 10% gel. Spot and displace all cement through 5 1/2" casing. 110 sxs. cement @ 1650' - 40 sxs. @ 850' - 70 sxs. @ 430'. Lay down 5 1/2" casing and fill hole.

Plugging Proposal Received by: Herb Deines - Marion J. Schmidt
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 5:30 P.M., Day: 25, Month: August, Year: 94

Actual plugging report: Kelso Casing ordered 250 sxs. 60/40 pozmix - 10% gel. Pumped in with pump truck - spotted and displace all cement through 5 1/2" casing.

1st. plug at 1650' w/110 sxs.

2nd. plug at 850' w/40 sxs.

3rd. plug at 430' w/70 sxs.

Load 8 5/8" casing to cellar.

Casing pulled by Kelso Casing - Chase, Kansas

RECEIVED
STATE CORPORATION COMMISSION
9-6-1994
SEP 06 1994

Remarks: Allied Cementing - Great Bend, Kansas
Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO
Bottom plug(in place): YES CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 1912 GL

CONSERVATION DIVISION
WICHITA, KANSAS

I did did not observe the plugging.

Marion J. Schmidt
(agent)

INVOICED
DATE SEP 12 1994
INV. NO. 41184