

4-060575

8-29

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-009-21,741-0000

SE NE SE /4 SEC. 33, 20 S, 14 W
1650 feet from S section line
330 feet from E section line

Operator license# 5363

Lease McGreevy 'B' well # 11

Operator: Berexco, Inc.

County Barton

Address: P.O. Box 723
Hays, Kansas 67601

Well total depth 3568 feet ^{115.96}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 817 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pullers, Inc. License# 6050

Address: P.O. Box 347 - Chase, Kansas 67524

Company to plug at: Hour: 2:00P.M. Day: 29 Month: August Year: 94

Plugging proposal received from: Mike Kelso/Manny

Company: Kelso Casing Pullers, Inc. Phone: 316-938-2943

Were: Order 225 sxs. 60/40 posmix - 10% gel and hulls.
Plug while pulling casing.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 5:00P.M., Day: 29, Month: August, Year: 94

Actual plugging report: 8 5/8" to 817' w/425 sxs. 5 1/2" to 3566' w/125
sxs. Sanded to 3500' and spotted 5 sxs. cement on top of sand with dump
bailer. Shot casing loose at 2600'. Pulled casing to 1650' and pumped
110 sxs. cement with 200# hulls. Pulled casing to 850' and pumped 40
sxs. with 100# hulls. Pulled casing to 430' and circulated cement with
50 sxs. Pulled casing with cement in cellar.


Remarks: Allied Cementing.

Condition of casing(in hole):GOOD X BAD Any plug: YES X NO

Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO

Plugged through TUBING , CASING X. Elevation: 1911 GL

I did [X] / did not [] observe the plugging.


10A (agent)

INVOICED
DATE 9-15-94
INV. NO. 41229