

4-060572

8-22

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-009-21,828-0000

SE SE SE /4 SEC. 33 , 20 S , 14 W  
330 feet from S section line  
330 feet from E section line

Operator license# 5363

Lease McGreevy 'B' well # 12

Operator: Berexco, Inc.

County Barton

Address: P.O. Box 723  
Hays, Kansas 67601

Well total depth 3563 feet <sup>115.80</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 818 feet

Aband. oil well X , Gas well     , Input well     , SWD     , D & A    

Plugging contractor: Kelso Casing Pullers, Inc. License# 6050

Address: P.O. Box 347 - Chase, Kansas 67524

Company to plug at: Hour: 1:00P.M. Day: 22 Month: August Year: 94

Plugging proposal received from: Mike Kelso/Manny

Company: Kelso Casing Pullers, Inc. Phone: 316-938-2943

Were: Order 225 sxs. 60/40 posmix - 10% gel and hulls.  
Plug while pulling casing.

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All[     ], Part[     ], None[ X ]

Completed: Hour: 5:30P.M. , Day: 22 , Month: August , Year: 94

Actual plugging report: 8 5/8" to 818' w/325 sxs. 5 1/2" to 3561' w/125 sxs. Sanded to 3500' and spotted 5 sxs. cement with dump bailer.  
Shot casing loose at 2724'. Pulled casing to 1650'. Pumped 110 sxs. cement with 200# hulls. Pulled casing to 850' and pumped 40 sxs. cement. Pulled casing to 430' and circulated cement to surface with 86 sxs. Pulled casing and topped with 10 sxs.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD     Anhy. plug: YES X NO      
Bottom plug(in place): YES X , CALC     , NO     Dakota plug: YES X , NO      
Plugged through TUBING     , CASING X . Elevation: 1911 GL    

I did     / did not X observe the plugging.

**INVOICED**

DATE 9-15-94

INV. NO. 41228

Herb Deines  
DA (agent)

Form CP-2/3

9-14-1994  
RECEIVED  
STATE CORPORATION COMMISSION

SEP 14 1994

CONSERVATION DIVISION  
WICHITA, KANSAS