

11-17 4-010317

15.009.20397.0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-009-20,403

NW NE NE /4 SEC. 26, 20 S, 14 W  
4950 feet from S section line  
990 feet from E section line

Operator license# 31995

Lease: Price Bondurant Well # <sup>1-V</sup>~~2-D~~

Operator: Midwest Investments

County: Barton 115.83

Address: Rt. 3 - Box 56  
Stafford, Kansas 67576

Well total depth 3564 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 808 feet

Aband. oil well  Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Allied Cementing / Quality Well Service License# 31925

Address: Russell, Kansas 67665

Company to plug at: Hour: 2:30 P.M. Day: 17 Month: November Year: 1997

Plugging proposal received from: Richard McIntyre

Company: Quality Well Service Phone: -

Were: Same as below.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 02 1997

CONSERVATION DIVISION  
Wichita, Kansas

12-2-1997

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[ ], Part[ X ], None[ ]

Completed: Hour: 5:00 P.M., Day: 17, Month: November, Year: 1997

Actual plugging report: Sanded to 3299'. Shot off pipe at 2458'. Pulled to 1575' and pumped 110 sxs 60/40 pozmix - 10% gel cement with 300# hulls. Pulled to 825' and pumped 40 sxs with 100# hulls. Pulled to 400' and circulated with 80 sxs. Topped off with 15 sxs.

Remarks:

Condition of casing(in hole): GOOD  BAD \_\_\_\_\_ Anhy.plug: YES  NO \_\_\_\_\_  
Bottom plug(in place): YES  CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES  NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_, CASING . Elevation: \_\_\_\_\_ GL

I did[ X ] / did not[ ] observe the plugging. *Car Martin*

(agent)  
Form CP-2/3

INVOICED

DATE DEC 09 1997

INV. NO. 149607

11-17 JAN 29 1998