

DISTRICT CONSERVATION AGENT'S REPORT

[Handwritten signature/initials]

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NE SE NE

SEC. 33 TWP. 20 RGE. 11W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease McGreevy

Operator Sunray Oil Co. Inc. Address Box 195 - Great Bend, Kansas

Field Bart-Staff County Barton

Total Depth 3640 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" Casing @ 834'. Circulated with 375 sacks cement, filled with
heavy mud to 275', set plug and ran 15 sacks through drill pipe and
filled with heavy mud and set plug @ 40', put in 1/2 sack of hulls on
top of plug and filled with 10 sacks of cement to top.

2-26-1952

FEB 26 1952

DISTRICT CONSERVATION DIVISION
Wichita, Kansas

Harold Hollis
District Conservation Agent

Date 2-23-52

PLUGGING
FILE SEC 33 T 20 R (11)
BOOK PAGE 147 LINE 6