

15.009.02063.0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 18 1973
CONSERVATION DIVISION
Wichita, Kansas

6-18-1973

J. Lewis Brock
Administrator
~~500 Business Building~~
Wichita, Kansas ~~67202~~

Operator's Full Name National Cooperative Refinery Association

Complete Address Box # 6, Great Bend, Kansas 67530

Lease Name McGreevy "B" Well No. # 4

Location NE NW SE Sec. 33 Twp. 20 Rge. 14 (E) (W) W

County Barton Total Depth 3627

Abandoned Oil Well Gas Well Input Well X SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Company

Address Box 364, Great Bend, Kansas License No. # 399

Operation Completed: Hour 4:30 P.M. Day 14 Month 6 Year 1973

The above well was plugged as follows:

8 5/8" csg. 836' Cwc. Perf. 3429'. Gas blow @ 1840'.

Sanded hole back to 3400' & dumped 5 sax cement with dump bailer. Circulated hole

with mud @ 1840' & displaced 100 sax cement @ 1625' with Halliburton Cementing

Company's pump truck. Pulled remaining pipe. Mud to 450', set 25' rock bridge.

& Displaced 6 vds. Ready-mix Cement, cementing from 425' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Don Thomas
Well Plugging Supervisor

DATE 6/19/73
INV. NO. 7523-U