

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUL 21 1978

CONSERVATION DIVISION  
Wichita, Kansas

7-21-1978

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 009-02064.0000 (of this well)

Operator's Full Name National Cooperative Refinery Assoc.

Complete Address Box 6 Great Bend Kansas 67530

Lease Name McGreevy "B" Well No. 5

Location SW NW SE Sec. 33 Twp. 20 Rge. 14 ~~(E)~~ (W) X

County Barton Total Depth 3618'

Abandoned Oil Well X Gas Well        Input Well X SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase, Kansas 67524 License No. 683

Operation Completed: Hour 3:30 PM Day 19 Month 7 Year 1978

The above well was plugged as follows:

Sanded back to 3325' and 5 sx cement with dump bailer.

Squeezed thru 8 5/8" surface casing with 4 sx hulls,

25 sx mud gel, plug, and 100 sx cement.

Max. pres. 700#. Shut in pres. 200#.

Recovered 2620' of 5 1/2" casing.

Plugged back to 3460'. Top perforation at 3364'.

3617' of 5 1/2" casing cemented with 125' sx cement.

845' of 8 5/8" surface casing cement circ.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Joan Rankin  
Well Plugging Supervisor

DATE 7-25-78

INV. NO. 7711-w