



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 89-20

LOCATION CSW-NW-NE

SEC. 27 TWP. 20 RGE. 12-W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Emma

Operator Phillips Petrol. Co Address Box 779 - G. Bend - Kans.

Field _____ County Barton

Total Depth 3518 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 282 ft - Circulated with cement
5 1/2" casing set at 3361 ft - Plugged back from bottom
to 3229 ft with cement - Filled with chert from 3229 ft to
3160 ft - Dumped 5 sacks of cement at 3160 ft - Shut off &
pulled the 5 1/2" casing - Filled with mud to 280 ft - Rock
Bridges & 15 sacks of cement at 280 ft - Mud to 30 ft -
Plug & 10 sacks of cement at the surface -

Went Supply Co RECEIVED
Plugging Contractors Conservation Div. 4-6-1949
APR - 6 1949 C. M. Stough -
District Conservation Agent

STATE CORPORATION
COMMISSION Date 4-4-49
KANSAS

PLUGGING
FILE SEC 27 T 20 R 1W
BOOK PAGE 89 LINE 20