

State of Kansas



15.135.20866.0000

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian

WICHITA, KANSAS 67217

RECEIVED  
STATE CORPORATION COMMISSIONVERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

APR 17 1974

CONSERVATION DIVISION  
Wichita, Kansas

4-17-1974

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Swope of Phillips Petro. has this date requested permission to plug the following described well:

Mr. Swope guarantees payment of the plugging fee.

Operator's full Name: Phillips Petroleum Co.

Complete Address: Box 287, Great Bend, Ks.

Lease Name: Sutton AB Well No. 1

Location: 1980' FEL & 660' FSL of NE/4 Sec. 15 Twp. 20 Rge. (E)(W) 23

County: Ness Total Depth 4480' Oil Well       

Gas Well        Input Well        SWD Well        D & A XX Lost Hole       

Mr. Sutton was instructed to plug the well as follows:

Gun pits, circulate heavy mud, displace 75 sk cem (4460-4260) thru

drill pipe. Heavy mud to 1100' -displace 50 sk cement (1100-1000)

thru drill pipe. Heavy mud to 560' -displace 50 sk cement (560-460)

Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

Very truly yours,

Leo R. Massey  
Conservation Division Agent