



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

SEP 13 1972

CONSERVATION DIVISION  
Wichita, Kansas

9-13-1972

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. C. W. Mosier of Kewanee Oil Company has this  
date requested permission to plug the following described well:

Mr. Kewanee Oil Company guarantees payment of the plugging fee.

Operator's full Name: Kewanee Oil Company

Complete Address: P. O. Box, 2093, Wichita, Kansas 67201

Lease Name: Lanter Well No. # 4

Location: NW SW SE Sec. 34 Twp. 20 Rge. 12 (E)(W) W

County: Barton Total Depth 3399 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Joe Clarke was instructed to plug the well as follows:

8 5/8" csg. 259' Cwc. Perf. 3196'.

Sanded hole back to 3150' & dumped 5 sax cement with dump bailer.

Pulled pipe. Squeezed well with 3 sax hulls, 15 sax mud, plug, &

100 sax cement with Halliburton Cementing Company's pump truck,

cementing from 340' to base of cellar.

Very truly yours,

Don L. ...  
Conservation Division Agent