

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

October 22, 1970

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 26 1970
CONSERVATION DIVISION
Wichita, Kansas

10-26-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Clyde Kuhn of Graves Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Kuhn guarantees payment of the plugging fee.

Operator's full Name: John C. Graves et al

Complete Address: 505 Union Center, Wichita, Kansas 67202

Lease Name: Gray Well No. 1

Location: SW NW NW Sec. 9 Twp. 18 Rge. 7 ~~(E)~~ (W) X

County: Rice Total Depth 3290' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Kuhn was instructed to plug the well as follows:

Fill hole with mud to 235'. Push plug and 1/4 sack hulls to 235' and
cement hole with 25 sacks cement through drill pipe. Fill hole with
mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10
sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,


Conservation Division Agent