

7-22

2-070720

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

## FEE FUND

API NUMBER: 15-159-01,002-0001

NE NW NE, SECTION 13 TOWNSHIP 20 RANGE 10W

OPERATOR LICENSE # 100

4950 FEET FROM S SECTION LINE

OPERATOR KANSAS CORPORATION COMMISSION

1650 FEET FROM E SECTION LINE

NAME &amp; 130 SOUTH MARKET #2125

ADDRESS WICHITA, KS 67202

LEASE NAME: BINGER #2

COUNTY: RICE

WELL TOTAL DEPTH: 3859'

PIPE: 5 1/2" @ 3388'

SURFACE CASING: 8 5/8" @ 150'

ABANDONED OIL WELL ☒ GAS WELL ☐ INPUT WELL ☐ SWD ☐ D&A ☐

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: D S &amp; W WELL SERVICING INC

ADDRESS: CLAFILIN, KS LICENSE: 6901

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 22 MONTH: 7 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: KENT STRUBE

COMPANY NAME: D S &amp; W WELL SERVICING INC PHONE: (316) 587-3361

WERE: PUMP 50 SACKS ON BOTTOM

1300', 35 SACKS

900', 35 SACKS

200' TO SURFACE

PLUGGING PROPOSAL RECEIVED BY: JACK LUTHI

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { ☒ } PART { ☐ } NONE { ☐ }

COMPLETED: HOUR: 4:00 DAY: 22 MONTH: 7 YEAR: 1997

ACTUAL PLUGGING REPORT: RAN A LINE, COULD ONLY GET TO 2000'. RAN TUBING IN TO 2000', VERY SOLID.  
PUMPED 200 LBS HULLS AND 50 SACKS OF CEMENT. PULLED TO 1300', PUMPED 35 SACKS. PULLED TO  
900', PUMPED 35 SACKS. PULLED TO 200', CIRCULATED CEMENT TO SURFACE IN AND OUT OF 5 1/2"  
CASING.

REMARKS: 60/40 POZ 4% GEL ALLIED #8284

I DID OBSERVE THIS PLUGGING.

JACK LUTHI

RECEIVED  
KANSAS CORPORATION COMMISSION  
AUG 18 1997  
CONSERVATION DIVISION  
WICHITA, KS  
8-18-1997