

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-20557-00-01  
Spot: NESESE Sec/Twnshp/Rge: 23-20S-24W  
990 feet from S Section Line, 330 feet from E Section Line  
Lease/Unit Name: PEMBER Well Number: 2  
County: NESS Total Vertical Depth: 4363 feet

Operator License No.: 31714  
Op Name: NOVY OIL & GAS, INC.  
Address: 125 N. MARKET STE. 1230  
WICHITA, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 9.625 feet: 321 WITH 225 SX CMT  
Production: Size 4.5 feet: 4360 WITH 100 SX CMT  
Liner: Size \_\_\_\_\_ feet: 3141.80

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/28/2001 1:20 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: PUMP 40 SX CMT & 200# HULLS AT 3400'. PERFORATE AT 750. RUN TUBING TO 1400' CIRCULATE CMT TO SURFACE. PULL TUBING. TIE ONTO CASING AND PUMP 80 SX CMT. TIE ONTO BACKSIDE AND PUMP 25 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER  
Date/Time Plugging Completed: 06/28/2001 4:10 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)  
KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 3400'. PERFS AT 4336-39' & 4247-50'. LEFT TUBING & TOOLS IN HOLE. GOT OUT OF CASING AT 3400'. PUMPED 40 SX CMT AND 200# HULLS AT 3400'. PERFORATED AT 750' RAN TUBING TO 1400' & CIRCULATED CMT TO SURFACE WITH 90 SX CMT. PULLED TUBING AND TIED ONTO CASING AND PUMPED 80 SX CMT. MAXIMUM PRESSURE 500#. SHUT IN WITH 400#. TIED ONTO BACKSIDE AND PUMPED 25 SX CMT. PRESSURE UP TO 500# AND HELD.

RECEIVED  
KANSAS CORPORATION COMMISSION

JUL 6 2001  
7-6-2001  
CONSERVATION DIVISION

INVOICED  
DATE 7-6-01  
INV. NO. 2002060017

Remarks: USED 60/40 POZMIX 65 GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Michael Maier  
(TECHNICIAN)

JUL 02 2001

Form CP-2/3