

To: 1090614
STATE CORPORATION COMMISSION
Wichita State Office Bldg. **PLUGGING SECTION**
130 S. Market, Room 2078
Wichita, KS 67202

15.135.30202.0000
10-20 API NUMBER 15- Completion date 4/20/66
SW NW NE, SEC. 23, T 20 S, R 24 W/E

990 feet from ~~NEX~~ section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6568
Operator: Kaiser-Francis Oil Company
Name: _____
Address P.O. Box 21468
Tulsa, OK 74121-1468

Lease Name Petersilie Well # A-4
County Ness 142.68
Well Total Depth 4390 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 259

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address P.O. Box 209, Chase, KS

Company to plug at: Hour: 12:35 p.m. Day: 20 Month: 10 Year: 1995

Plugging proposal received from David
(company name) Mike's Testing & Salvage (phone) 316-938-2943
were: 5 1/2" at 4382' w/100 sx cement, Open hole 4382-90'

CIBP set at 4340',
1st plug pull casing to 800' and pump 50 sx cement with 6 sx gel,
2nd plug at 300' with 50 sx cement,
3rd plug at 40' with 10 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 20 Month: 10 Year: 1995

ACTUAL PLUGGING REPORT 1st plug CIBP set at 4340',
2nd plug pulled casing to 800' and spotted 50 sx cement with 6 sx gel,
3rd plug pulled to 300' and spotted 50 sx cement,
4th plug pulled to 40' and spotted 10 sx cement.

Rec'd KCC
OCT 30 1995
10-30-1995

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1518' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (and/or MAX) observe this plugging.

DATE 11-1-95

Signed [Signature]
(TECHNICIAN)

INV. NO. 43924