

1 050567

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,005-0000

C SW SW, SEC. 33, T 20 S, R 20 (W) X

660 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8778

Lease Name Steffen Well # 1

Operator: Midwestern Supply Co., Inc.

County Pawnee 136.50

Name & Address 300 Patton Road

Well Total Depth 4200 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 325

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 am Day: 5 Month: July Year: 19 85

Plugging proposal received from Millard Kelso

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 4198'

1st plug plug 1 sack hulls and 50 sx cement, 10 sx gel, 50 sx cement, 5 sx gel and 125 sx cement.

Pump 100 sx cement down the annulus

RECEIVED
STATE CORPORATION COMMISSION

Plugging Proposal Received by Paul A. Luthi

7-9-1985 (TECHNICIAN)

Plugging Operations attended by Agent?: All CONSERVATION DIVISION Wichita, Kansas None

Operations Completed: Hour: 1:00 pm Day: 5 Month: July Year: 19 85

ACTUAL PLUGGING REPORT Pumped down 5 1/2" with 1 sack hulls, 50 sx cement, 10 sx gel,

50 sx cement, 5 sx gel and 125 sx cement. Pumped 15 sx cement down 8 5/8" annulus

5 1/2" - maximum pressure 600 psi - Annulus pressure maximum 900 psi and shut in 900 psi shut in pressure 200 psi

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(did / state) observe this plugging.

DATE 7-17-85

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 9012