

1 030339

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-21,037 - 0000 ^R

NW/4 SEC. 11, T 30 S, R 18 W/X

3310 feet from S section line

3420 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Kane "B" Well # 1

Operator: TXO Production Corp.

County Kiowa 162.83

Name & Address 200 W. Douglas, Suite 300

Well Total Depth 5010 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 468

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00 am Day: 28 Month: November Year: 19 84

Plugging proposal received from Norman Voth

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 5007' PBSD 4900' Perfs from 4767'-80'

1st plug pump 35 sx cement and push plug to 4500'

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 125 sx cement.

Plugging Proposal Received by A. Tom Blument
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 pm Day: 28 Month: November Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 5007' PBSD 4900' Perfs from 4767-80'

1st plug pumped 35 sx cement to bottom and pushed plug to 4500', 2nd plug squeezed well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Maximum pressure 1000 psi and shut in 800 psi

10-5-84
DEC 05 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun. Recovered 2515' 4 1/2" casing
(If additional description is necessary, use BACK of this form.)

INVOICED (did / did not) observe this plugging.

Signed A. Tom Blument
(TECHNICIAN)

DATE 12-12-84

INV NO 5928