

1 010009

097 15-097-20931-001  
017-20,931-0001

API NUMBER 15- 017-20,931-0001

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C SE NE, SEC. 14, T 30 S, R 18 W/EX

3300 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Kane "C" Well # 1

Operator: TXO Production Corp.  
Name & Address 200 W. Douglas, Suite 300  
Wichita, KS 67202

County Kiowa 166.79

Well Total Depth 5132 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 536

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Oilfield Services License Number 5105

Address P. O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:00 am Day: 10 Month: July Year: 19 85

Plugging proposal received from John Clarke

(company name) Clarke (phone) 316-886-5665

were: 4 1/2" at 5130' PBSD 5010' Perfs at 4968-86'

1st plug sand back to 4916' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 125 sx cement.

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:30 am Day: 10 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4916' and dumped 4 sx cement on top of

sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel,

1 sack hulls, released 8 5/8" rubber plug and pumped an additional 125 sx cement.

Maximum pressure 500 psi and shut in 250 psi

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan. Recovered 4400' 4 1/2" casing  
(If additional description is necessary, use BACK OF COMPLETION FORM.)

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 22 1985  
7-22-1985

INVOICED

observe this plugging.

DATE 7-24-85

Signed Paul A. Luthi  
(TECHNICIAN)

INV. NO. 9105