

1 030144

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 097-21,008 - 0000  
SW SE, SEC. 21, T 30 S, R 18 WXX  
660 feet from ~~W~~/S section line  
1980 feet from ~~W~~/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Smith "QQ" Well # 1

Operator: TXO Production Corp.

County Kiowa

Name & Address 200 West Douglas, Suite 300

Well Total Depth 5150 167.38 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 436

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&XX \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor H-30 Drilling, Inc. License Number 5107

Address 251 North Water, Wichita, KS 67202

Company to plug at: Hour: 3:00 pm Day: 27 Month: March Year: 19 84

Plugging proposal received from Gerald Veatch

(company name) TXO (phone) 316-265-9441

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1120' with 50 sx cement

2nd plug at 560' with 50 sx cement  
solid bridge

3rd plug hulls' - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 15 sx cement

6th plug to circulate mousehole with 10 sx cement

Plugging Proposal Received by Steve Plumont  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 6:15 pm Day: 27 Month: March Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1120' with 50 sx cement, 2nd plug at 560' with

50 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to

surface with 10 sx cement, 5th plug to circulate rathole with 15 sx cement, 6th plug

to circulate mousehole with 10 sx cement

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Dowell

(If additional description is necessary, use BACK of this form.)

(If additional description is necessary, use BACK of this form.) observe this plugging.

INVOICED

DATE 4-4-84

Signed Steve Plumont  
(TECHNICIAN) ✓

REV. NO. 1065 3-77

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 29 1984  
CONSERVATION DIVISION  
Wichita, Kansas