

1 060807

271 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-20,431-0000

C SW NW , SEC. 22 , T 30 S, R 18 W/E
3300 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6234

Lease Name Dorsett Well # 1

Operator: The Maurice L. Brown Company
Name & Address: 200 Sutton Place Building
Wichita, KS 67202

County Kiowa 163.164

Well Total Depth 5035 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 555

Abandoned Oil Well Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address 107 W. Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 11:00 am Day: 17 Month: February Year: 19 86

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 5 1/2" at 5020' PBTD 4680' Perfs at 4571-74'

1st plug sand back to 4520' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,
release 8 5/8" rubber plug and pump 125 sx cement,

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:00 pm Day: 17 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4520' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel 1 sack hulls, released 8 5/8" rubber plug and pumped 125 sx cement.

Maximum pressure 400 psi and shut in 300 psi

Remarks: Recovered 2582' 5 1/2" casing. Used 60/40 Pozmix 2% gel 2% cc by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED
FEB 27 1986

DATE _____

INV. NO. 12719

APR 10 1986

2-24-1986
RECEIVED
STATE CORPORATION COMMISSION
FEB 24 1986
CONSERVATION DIVISION

Signed Paul A. Luther (TECHNICIAN)

2-24-86