

1 070251

119
2

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,071-0000
NW NE NW SEC. 15, T 20 S, R 23 W/E
4950 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5923

Lease Name Burditt Well # 1

Operator: American Petroleum Company, Inc.
Name & Address 400 N. Woodlawn, Suite 111
Wichita, KS 67208

County Ness 141.02

Well Total Depth 4339 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 428

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil Operations License Number 8241

Address Box 506, Russell, KS 67665

Company to plug at: Hour: 8:30 a.m. Day: 22 Month: 11 Year: 1986

Plugging proposal received from Hap Halfhill

(company name) Emphasis Oil Operations (phone) 913-483-5345

were: to fill hole with heavy mud and spot cement through drill pipe
Elevation 2258' GL
Anhydrite 1490-1530'

1st plug at base Anhydrite with 50 sx cement, 2nd plug at base Dakota with 80 sx cement,

3rd plug at 380' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement, 6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 11 a.m. Day: 22 Month: 11 Year: 1986

ACTUAL PLUGGING REPORT 1st plug at 1530' with 50 sx cement,

2nd plug at 800' with 80 sx cement,

3rd plug at 460' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. 11-25-1986

(If additional description is necessary, use BACK of this form.)

INVOICED

(If applicable) observe this plugging.

DATE 11-25-86

Signed Dan Goodrow
(TECHNICIAN)

INV. NO. 15427

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date NOVEMBER 20 1986 month day year

API Number 15- 135-23,071.0000

OPERATOR: License # 5923 AMERICAN PETROLEUM COMPANY, INC. Name Address 400 N. WOODLAWN, SUITE 111 City/State/Zip WICHITA, KANSAS 67208 Contact Person JAMES T. BARVAIS Phone (316) 684-5273

NW. NE. NW. Sec. 15 Twp. 20 S, Rg. 23 X West 4950 Ft. from South Line of Section 3630 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330 feet County NESS

CONTRACTOR: License # 8241 EMPHASIS OIL OPERATIONS Name Address RUSSELL, KANSAS 67665

Lease Name BURDITT Well # 1

Ground surface elevation 2258 feet MSL

Domestic well within 330 feet: yes X no

Municipal well within one mile: yes X no

Well Drilled For: X Oil SWD Infield Mud Rotary Gas Inj X Pool Ext Air Rotary OWWO Expl Wildcat Cable

Depth to bottom of fresh water 75 feet

Depth to bottom of usable water 350 feet

Surface pipe by Alternate: 1 X 2

Surface pipe planned to be set 350'

Conductor pipe required NO

Projected Total Depth 4450 feet

Formation MISSISSIPPI

If OWWO: old well info as follows:

Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 11-6-86 Signature of Operator or Agent Title PRESIDENT

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 350 feet per Alt.

This Authorization Expires 5-7-87 Approved By 11-7-86

Spud 11-15-86

Handwritten signatures and notes including 'Kch 2640' and 'NO W.W.' in a circle.

PER DODGE CITY 11-7-86

NW. NE. NW. Sec. 15 Twp. 20 S, Rg. 23 X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with columns for plug depth, material (ANHYDRITE, BASE DAKOTA), and casing size (60/40 POZMIX, 6% GEL).

Vertical log entries: PUSHER Kap WALENICK, TD 4339 FORMATION, SURFACE PIPE 4337 length 858" @ 428', ANHYDRITE 1490'-1530' ELEVATION, COMPLETION TIME & DATE 11:00AM 11-22-86, 1st PLUG @ 1530 FT. W/ 50 SX, 2nd PLUG @ 800 FT. W/ 80 SX, 3rd PLUG @ 460 FT. W/ 40 SX, 4th PLUG @ 40 FT. W/ 10 SX, RAT HOLE CIRCULATED W/ 15 SX, MOUSE HOLE CIRCULATED W/ 10 SX, 60/40 pos. 6% gel WATER WELL PLUGGED W/ SX

Vertical log entries: (b) Mousehole with 10 SX, CEMENT COMPANY Allied, TECHNICIAN D.G., NOV 23 1986