

1060122

TO: STATE CORPORATION COMMISSION

9-29

API NUMBER 15-135-20,820-0000
C SE SW SEC. 15, T 20 S, R 23 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3300 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME REINERT "B" WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY NESS

OPERATOR LICENSE # 100 WELL TOTAL DEPTH 4500 FEET

OPERATOR: KCC FEE FUND #990022-001 PRODUCTION CSG: SIZE 4 1/2 " FEET 4439

NAME AND 130 S MARKET RM 2078 SURFACE CASING: SIZE 8 5/8 " FEET 439'

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HERBINAFTER INDICATED

PLUGGING CONTRACTOR ALLIED CEMENTING COMPANY, INC LICENSE NUMBER N/A

ADDRESS PO BOX 31, RUSSELL, KS 67665-0031

COMPANY TO PLUG AT: HOUR: 2:20 PM DAY: 29 MONTH: 09 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM MIKE MAIER

(COMPANY NAME) KCC (PHONE) 316-225-8888

WERE: PERFS AT 4362-69

PUMP 25 SX CEMENT AND 200# HULLS THEN 250 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 3:00 PM DAY: 29 MONTH: 09 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG PUMPED 200# HULLS THEN 275 SX CEMENT. CEMENT PRESSURED TO 500# AND SHUT IN WITH

500#. PUMPED DOWN BACKSIDE PRESSURED INSTANTLY TO 500#.

RECEIVED
CONSERVATION DIVISION
Wichita Kansas
DEC 11 1998

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED. 12-31-1998

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Michael J. Maier (TECHNICIAN) FORM CP-2/3