

6070427 **PLUGGED**

API NUMBER 15-009-05645-0001 *R*

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE, SEC. 34, T. 20 S, R. 12 *W*
330 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT (4519)

Operator License # 5816
Operator: CHEVRON U.S.A. Inc.
Name & Address: P.O. Box 12116
Oklahoma City, OK.
73157

Lease Name Lang Well # 5-X
County Bartox, Co 131.33
Well Total Depth 4041 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 261

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cementing Co License Number _____

Address East. Hwy 40 Days, Naho 67601

Company to plug at: Hour: 11:00 AM Day: 5th Month: Dec Year: 19 85

Plugging proposal received from Dan Massingill

(company name) Chevron USA, Inc (phone) _____

were: 8 5/8" - 261' SW CUC 1/150 cmt, 5 1/2" cas set @ 4008' 1/600 cmt.
Well squeezed @ 1993' 1/1794' cmt CMT circulated, Packer @ 2586'
Csg Packed @ 1160', Fish at 1960'. Made an attempt to get down.
(SWD) was taking fluid, Ordered 900' Class A 2% Gel, 8" Cells Slake.
Run in Tubing Circulate Cement and Squeeze, Pressure Annulus with
Cement,

Plugging Proposal Received by Marion Schmitt
Doic (TECHNICIAN)

Plugging Operations attended by Agent: All X Part _____ None _____

Operations Completed: Hour: 2:00 PM Day: 5th Month: Dec Year: 19 85

ACTUAL PLUGGING REPORT Ordered 900' Class A 2% Gel, 8" Cells Slake
and 4" CaCl, Ran 2 7/8" tubing to 1154', Pumped in
450' cmt 1/5" Cells Slake, Cement Circulated @ 450' cement,
Tied on to Annulus Pressured to 500 Psig 1/ approx 3' cmt - Shut in @ 275'
tie/d down tubing, Pumped in 5 1/2" cas 1/200' cmt, 250 Psig, Pumped
in another 200' cmt, 250 Psig, Cemented By Halliburton Cmt.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE DEC 18 1985

INV. NO. 11591

DEC 16 1985
12-16-1985
CONSERVATION DIVISION
Wichita Kansas

JAN 15 1986

Signed Marion Schmitt
Doic (TECHNICIAN)

FORM CP-2/3
Rev. 01-84