

4-060844

2-22

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-009-23,638.0000

SW SE NW /4 SEC. 34, 20 S, 12 W  
2970 feet from S section line  
3630 feet from E section line

Operator license# 31528 Lease: Walters Well # 1

Operator: Mike Kelso Oil, Inc. County: Barton

Address: P.O. Box 209 Well total depth 3433 111.57 feet  
Chase, Kansas 67524 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 287 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: P.O. Box 209 - Chase, Kansas 67524

Company to plug at: Hour: 3:00 P.M. Day: 22 Month: February Year: 1996

Plugging proposal received from: Mike Kelso

Company: Mike's Testing & Salvage, Inc. Phone: 316-938-2943

Were: Order 225 sxs 60/40 posmix - 10% gel and hulls. 2-29-1996  
Plug while pulling casing.  
Emergency permission to plug with rig over hole.

RECEIVED  
KANSAS CORP COM  
FEB FEB 29 A 11:16

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All [ ], Part [ ], None [ X ]

Completed: Hour: 5:00 P.M., Day: 22, Month: February, Year: 1996

Actual plugging report: 8 5/8" to 287' w/260 sxs. 5 1/2" to 3427' with 125 sxs. Perfs at 3212' - 3216'. Sanded to 3160' and spotted 5 sxs cement with dump bailer. Shot casing loose at 2520' and pulled to 1475'. Mixed and pumped 100 sxs cement with 300# hulls. Pulled casing to 700' and pumped 35 sxs cement with 200# hulls. Pulled casing to 325' and circulated cement to surface with 70 sxs. Pulled casing and topped with 15 sxs.

Remarks: Allied Cementing.  
Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO  
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO  
Plugged through TUBING, CASING X. Elevation: 1836 GL

I did / did not [ X ] observe the plugging.

Herb Deines (agent)

INVOICED  
DATE MAR 05 1996  
INV. NO. 44944