

3-11-88

6 061450

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-009.05226.0001
NE NE SE, SEC. 33, T 20 S, R 12 W/E
2310 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5245
Operator: Okmar Oil Co.
Name & Address: Box 723
Hays, Kansas 67601

Lease Name Kasselman Well # B-2 SWD
County Barton 115.80
Well Total Depth 3563 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 287

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor B. J. Titan License Number

Address R. R. Ave Great Bend, Ks. 67530

Company to plug at: Hour: 10:00 AM Day: 11 Month: March Year: 19 88

Plugging proposal received from George Jorgensen

(company name) Okmar Oil Co. (phone) 913-628-610.

were: Order 50 sks Common and 300 sks.

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:00 PM Day: 11 Month: March Year: 19 88

ACTUAL PLUGGING REPORT 8 5/8" set at 287' w/190 sks. 5 1/2" set at 3506' w/150 sks.

Top perf at 3247'. Ran 2" rubing to top of fish, pumped 50 sks Common. Pulled 400' of tubing.

Pumped down tubing and circulated w/50 sks Econolite. Pulled out tubing and pumped down 5 1/2"

200 sks cement w/700 Psig. Pumped in 8 5/8" - 50 sks cement w/600 Psi.

RECEIVED
STATE CORPORATION COMMISSION
3-25-1988
MAR 25 1988

Remarks: Perf at Anhy and 2400' and 610'. Plastic tubing lost in hole w/top of fish at 2400'.
(If additional description is necessary, use BACK of this form.)

INVOICED
(did not observe this plugging.)

Signed Gilbert G. Scheck
(TECHNICIAN)

DATE 3-29-88
INV. NO. 20252