

5-21

2-

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-159-20,877.00.00

E/2 SE SE, SECTION 31 TOWNSHIP 18 RANGE 6W

OPERATOR LICENSE # 6141 660 FEET FROM S SECTION LINE
330 FEET FROM E SECTION LINE

OPERATOR Coronado Oil & Gas Inc.
NAME & ADDRESS P.O.Box 1285 50 Main Street
Great Bend KS 67530 White Plains, Ny 10606

RECEIVED
KANSAS CORPORATION COMMISSION
6-4-1993
JUN 04 1993

LEASE NAME: Fail #1
COUNTY: Rice
WELL TOTAL DEPTH: 3205 104.16
PIPE: 4-1/2" @ 3105'/175sx
SURFACE CASING: 8-5/8" @ 210'

CONSERVATION DIVISION
WICHITA, KS

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SWD _____ D&A _____
OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Kelso Casing & Pulling
ADDRESS: P.O.Box 347 Chase KS 67524 LICENSE: 6050

COMPANY TO PLUG AT: HOUR: _____ am DAY: 21 MONTH: 5 YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: Manny

COMPANY NAME: Kelso Casing & Pulling PHONE: 316-938-2943
WERE: Sand to 2900'- cap w/ 4sx cmt- shoot pipe- pull csq
to 950'- 35sx cmt- Pull csq to 600;- 35sx cmt- pull csq
to 260'-circ cmt to surface.

PLUGGING PROPOSAL RECEIVED BY: Dist. #2

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (X) PART (_____) NONE (_____)

COMPLETED: HOUR: 11:30a DAY: 21 MONTH: 5 YEAR: 1993

ACTUAL PLUGGING REPORT:
Sanded to 2900'- capped w/ 4sx cmt- Shot pipe- Pulled
csq to 970'- loaded hole w/ 19bbls water- 35sx cmt-
pulled csq to 616'- 35sx cmt- pulled csq to 264'- circ
65sx cmt to surface.
Perf: 2960-68', 3023-28' Rec 2220' -

REMARKS: Allied Cmt #3131-60/40 poz 4% gel

INVOICED

I DID OBSERVE THIS PLUGGING.

DATE 6-7-93
INV. NO. 37843

R. Phil Worley
R. Phil Worley (AGENT)

rw