

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

10-25

API NUMBER: 15-159-22,219,00.00

N/2 NW SW, SECTION 18 TOWNSHIP 18 RANGE 6W

OPERATOR LICENSE # 5120 2310 FEET FROM S SECTION LINE  
OPERATOR RANGE OIL COMPANY, INC. 660 FEET FROM W SECTION LINE  
NAME & 125 NORTH MARKET, SUITE 1120  
ADDRESS WICHITA, KS 67202

LEASE NAME: REHME #1  
COUNTY: RICE 105.23  
WELL TOTAL DEPTH: 3238'  
PIPE: 4 1/2" @ 3237' - 75 SACKS  
SURFACE CASING: 8 5/8" @ 233'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD  D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE  
ADDRESS: CHASE, KS 67524 LICENSE: 31529

COMPANY TO PLUG AT: HOUR: PM DAY: 25 MONTH: 10 YR: 1996

PLUGGING PROPOSAL RECEIVED FROM: MANNY  
COMPANY NAME: MIKE'S TESTING & SALVAGE PHONE: (316) 938-2943  
WERE: SAND TO 3065' WITH 4 SACKS OF CEMENT. SHOOT PIPE. PULL CASING TO 950'  
WITH 35 SACKS OF CEMENT, PULL CASING TO 350'. CIRCULATE CEMENT TO SURFACE.

RECEIVED  
KANSAS CORPORATION COMMISSION

NOV 04 1996  
11-4-1996

PLUGGING PROPOSAL RECEIVED BY: DISTRICT #2

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL {  } PART {  } NONE {  }

CONSERVATION DIVISION  
WICHITA, KS

COMPLETED: HOUR: 4:00PM DAY: 25 MONTH: 10 YEAR: 1996

ACTUAL PLUGGING REPORT: SANDED TO 3065' AND CAPPED WITH 4 SACKS OF CEMENT. SHOT  
PIPE, PULLED CASING TO 963', LOADED HOLE, 35 SACKS OF CEMENT AND 100# HULLS,  
PULLED CASING TO 350'. CIRCULATED 100 SACKS OF CEMENT TO SURFACE.

REC. 2031'

REMARKS: 60/40 POZ 4% GEL ALLIED CEMENTING #5038

I DID OBSERVE THIS PLUGGING.

R. Phil Worley  
R. PHIL WORLEY

INVOICED  
NOV 06 1996  
DATE  
INV. NO. 46914

W