

15.009.00333.0000

P

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - -

RECEIVED
STATE CORPORATION COMMISSION
JUN 14 1978
CONSERVATION DIVISION
Wichita, Kansas

6-14-1978

Operator's Full Name Duke Drilling Co.

Complete Address Box 323 Great Bend, Kansas 67530

Lease Name Kasselman Well No. 1

Location NW SE SE Sec. 33 Twp. 20 Rge. 12 ~~SW~~ (W) X

County Barton Total Depth 3406'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase, Kansas 67524 License No. 683

Operation Completed: Hour 11:15 AM Day 13 Month 6 Year 1978

The above well was plugged as follows:

Sanded back to 3300' and 5 sx cement with dump bailer.

Squeezed thru 8 5/8" surface casing with 4 sx hulls,

25 sx mud gel, 1 sx hulls, plug, and 100 sx cement.

Max. pres 500#. Shut in pres. 150#. Plugged back to 3351'.

Recovered 2504' of 5 1/2" casing. Top perforation at 3322'.

3404' of 5 1/2" casing cemented with 100 sx cement.

248' of 8 5/8" surface casing cement circ.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Duane J. Rankin
Well Plugging Supervisor

DATE 6-14-78

INV. NO. 7481-0