

15.009.15647.0000

Form CP-3
Rev. 6-26-62

16
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

DEC 7 1964
12-7-1964
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Morgenstern & Specter

Complete Address: Box 661, Russell, Kansas

Lease Name Workman Well No. # 2

Location SE NE NE Sec. 33 Twp. 20 Rge. 12 (E) W

County Barton Total Depth 3459

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Lynch's Casing Pulling

Address: R.R. # 4, Great Bend, Kansas License No. 457

Operation Completed: Hour 12 AM Day 2 Month 12 Year 1964

The Above well was plugged as follows:

8 5/8" 270' Cwc.

Sanded hole back to 3400' & dumped 5 sax cement with dump bailer.

Pulled pipe. Mudded hole to 260'; set rock bridge & dumped 5 sax cement
with dump bailer. Let set over-nite. Bailed hole dry; displaced 20 sax
cement. Mud to 40'; set rock bridge; displaced 10 sax cement, cementing
to base of cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 12/4/64
INV. NO. 288-W

Signed: Don Tolson
Well Plugging Supervisor