

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 70-14LOCATION CSE-SE-22ESEC. 33 TWP. 20 RGE. 12-WDry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease WorkmanOperator Lavin Oil & Gas Co. Address #301 S. West St. Wichita - Kans.Field _____ County BartonTotal Depth 3498 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2 - 244 ft. Pipe isolated with cement.
4 1/2" casing set at 3421 ft. Cemented with 75 sacks cement
Plugged back to 3400 ft with 99 cbl. - Pumped
4 sacks of cement at 3400 ft. Shot off & pulled the
4 1/2" casing - Filled hole with mud - Pumped in
Plug & 100 sacks of cement - filling hole from 325 ft
to the surface with cement - cement pumped in
by Globe Oil Well Cementing Co
Standard Pipe Pulling Co. Plugging Contractors

RECEIVED
STATE CORPORATION COMMISSION

APR - 6 1951

District Conservation Agent
Conservation Division
Wichita, KansasDate 4-4-51

PLUGGING

FILE SEC 33 T 20 R 12-W
BOOK PAGE 72 LINE 14

4-6-1951