

KANSAS

FORM CP-3  
Rev. 1-8-82

## STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT REPORT

API Number 15-159-20,721.00.00200 Colorado Derby Building  
Wichita, KS 67202Operator's Full Name R. & B. Petroleum Inc.Complete Address Box 1285, Great Bend, Kansas 67530Lease Name Voith Well No. 1Location SE SE NW Sec. 18 Twp. 18 Rge. 6 (East) (West)County Rice Total Depth 3300'Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☒

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling and Allied Cementing Co., Inc.Address Box 126, Chase, Kansas License No. 683Operation Completed: Hour: Noon Day: 10 Month: May Year: 19 82Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐The above well was plugged as follows: 4 1/2" - 3298 - 160 sacks  
PB-TD-3242 Per F 3210-18'Hole Filled with sand to 3150' and cemented with 4 sacks cement.  
Hole squeezed with 5 sacks hulls, 25 sacks gel., 8 3/8" plug,  
and 100 sacks 50/50 Pozmix w/2% gel and 3% C.C. pumped into  
8 3/8" surface casing.2636' of 4 1/2" casing recoveredAmount of Surface Casing: 8 3/8" - 218' - 165 sacks

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: \_\_\_\_\_  
Conservation Division Agent  
STATE CORPORATION COMMISSION

INVOICED

DATE 5-19-82INV. NO. 208-W

MAY 19 1982

CONSERVATION DIVISION  
Wichita, Kansas

5-19-1982