

STATE OF KANSAS
STATE CORPORATION COMMISSION
30 S. Market, Room 2078
Wichita, KS 67202

K.A.R.-82-3-117

API NUMBER 15-159-22,219 00.00

LEASE NAME Rehme

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

LEASE OPERATOR Range Oil Company, Inc.

SEC. 18 TWP. 18 RGE. 6W (E) or (W)

ADDRESS 125 N. Market, Ste 1120 Wichita, KS 67202

COUNTY Rice

PHONE (316) 265-6231 OPERATORS LICENSE NO. 5120

Date Well Completed

Character of Well Oil

Plugging Commenced 10-24-96

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-25-96

The plugging proposal was approved on (date)

by Phil Worley (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3238'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	233'	none
				4 1/2	3237'	2031'

11-8-1996
KANSAS
STATE
CORPORATION
COMMISSION
WICHITA, KS
67202

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material was used, state the character of same and depth placed, from feet to feet each side. Sanded off bottom to 3065' & ran 4 sks cement. Shot at 2516', 2331', & 2031'. Pipe came loose at 2031'. Pulled to 950', pumped 35 sks cement w/100# hulls. Pulled to 390', pumped 100 sks cement & circulated to surface. Pulled rest of pipe. Plugging complete. 60/40 4%.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Range Oil Company, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 7th day of November, 19 96

[Signature]
Notary Public

My Commission Expires:

