

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

NORTH



Locate well correctly on above
Section Plat

Rice County. Sec. 27 Twp 18 Rge. 7 ~~X~~ (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines SE 1/4 NE 1/4 NE 1/4
Lease Owner Solar Oil Corporation
Lease Name Coral Sellers Well No. 1
Office Address 1117 Union National Bank Building, Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 2, 1951 19
Application for plugging filed August 2, 1951 19
Application for plugging approved August 2, 1951 19
Plugging commenced August 3, 1951 19
Plugging completed August 3, 1951 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation Depth to top Bottom Total Depth of Well 3441 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	159.44	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from 3441 feet to surface feet for each plug set.

Run one-half drill pipe in hole - came out laying down.
Run second half drill pipe - pumped hole full of heavy mud.
Set firm rock bridge at 150'.
Run 15 sacks cement through 5 joints drill pipe.
Pumped heavy mud to 5'. Set wood bridge and filled
with cement to bottom of cellar, requiring 5 sacks cement.

RECEIVED 8-24-1951
STATE CORPORATION COMMISSION
AUG 24 1951

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Solar Oil Corporation
Address 1117 Union National Bank Building, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
James Davis, Jr., (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

James Davis, Jr.

(Address)

SUBSCRIBED AND SWORN to before me this 13th day of August, 1951.

Leata Lee Miller

Notary Public.

My commission expires July 27, 1955



PLUGGING
FILE SEC 28 T 18 R 7W
BOOK PAGE 101 LINE 14

WELL LOG

SELLERS #1

SE/4 NE/4 NE/4 Section 27- Township 18S- Range 7W, Rice County, Kansas

Figures indicate Bottom of formation:

	0 -	60 sand & clay
		145 shale
		161 red rock & shale
		172 anhydrite
Well Commenced 7-18-51		350 red brd & shale
Well completed 8-3-51		825 shells & shale
162' 8 5/8" surface pipe set		855 salt & shale
		1095 shale & shells
		1595 Lime & shale
		2020 shale & lime
		2642 lime & shale
		2818 shale & lime
		2889 lime
		2952 lime K. C.
		3150 lime
		3182 conglomerate
		3265 lime
		3276 shale
		3315 lime
		3441 lime & shale - total depth

STATE OF _____, COUNTY OF _____

_____ contractor of the above-described well, being first duly sworn on oath says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above -described well and that the same are true and correct.

(Signature) _____

(address) _____

SUBSCRIBED AND SWORN TO before me this _____ day of _____ 19 _____

Notary Public

My Commission expires _____

RECEIVED
STATE CORPORATE COMMISSION
AUG 24 1951
CONSE

PLUGGING
FILE SEC 28 T 18 R 7W
BOOK PAGE 10 LINE 14