


STATE OF KANSAS  
STATE-CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavits  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Rice County. Sec. 26 Twp. 18S Rge. 7 ~~XX~~ (W)

Location as "NE/CNW%SW%" or footage from lines SW SW NE  
Lease Owner H-30, Inc.  
Lease Name O'Hara Well No. 1  
Office Address 200 North Main, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed April 8, 19 64  
Application for plugging filed April 8, 19 64  
Application for plugging approved April 8, 19 64  
Plugging commenced April 8, 19 64  
Plugging completed April 8, 19 64  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation Depth to top Bottom Total Depth of Well 3,482 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	217'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud to 210 feet. Set bottom plug at 210 feet and cemented with 20 sacks cement and 1/3 sack hulls. Filled hole with heavy rotary mud to 40 feet. Set top plug at 40 feet and cemented with 10 sacks cement and 1/3 sack hulls.

RECEIVED  
STATE CORPORATION COMMISSION

APR 15 1964

4-15-1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor H-30, Inc.  
Address 200 North Main, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Garnet B. Douthit (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) Garnet B. Douthit  
200 North Main, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 13th day of April, 19 64  
Geraldine Hays Notary Public

My commission expires December 3, 1964.




KANSAS GEOLOGICAL SOCIETY  
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
 KANSAS GEOLOGICAL SOCIETY BUILDING  
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY H-30, Inc.  
 FARM O'Hara NO. 1

SEC. 26 T18S R. 7W  
 LOC. SW SW NE

TOTAL DEPTH 3,482'  
 COMM. 3-30-64 COMP. 4-8-64  
 SHOT OR TREATED  
 CONTRACTOR H-30, Inc.  
 ISSUED

COUNTY Rice



CASING  
 20 10  
 18 5 5/8" 217' cem. w/140 sx.  
 12 6  
 13 5

ELEVATION 1672 GR  
 1674 DF  
 1677 KB  
 PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Native soil	30
Shale & shells	175
Post rock	218
Shale & Shells	1265
Shale & lime strks	1335
Lime	1435
Lime & Shale	1855
Shale & Lime	2415
Lime & Shale	2540
Shale & Lime	2755
Lime & Shale	2895
Lime	3168
Lime & Sand	3210
Lime	3250
Shale & Lime	3325
Shale & Lime (cherty)	3379
Lime & Shale	3430
Lime	3482
Rotary T. D.	3482

Sample Tops

Topeka	2308	- 631
Heebner	2587	- 910
Base Oread	2595	- 918
Toronto	2616	- 939
Douglas	2630	- 953
Br. Lime	2712	-1035
Lansing	2753	-1076
Congl. Sand	3172	-1495
Cherty Congl.	3193	-1516
Kinderhook Shale	3216	-1539
Kinderhook Sand	3235	-1558
Maquoketa Shale	3268	-1591
Maquoketa Dolomite	3308	-1631
Viola	3360	-1683
Simpson	3393	-1716
Arbuckle	3465	-1788
Rotary T. D.	3482	-1805

RECEIVED  
 STATE CORPORATION COMMISSION

APR 15 1964

CONSERVATION DIVISION  
 Wichita, Kansas

I hereby certify that the above and foregoing is a true and correct log of the above described well, as shown by the drilling reports.

H-30, INC.

*Garnet B. Douthit*  
 Garnet B. Douthit

STATE OF KANSAS )  
 ) SS:  
 SEDGWICK COUNTY )

Subscribed and sworn to before me, a Notary Public in and for said county and state, this 13th day of April, 1964.

My Commission Expires:  
 12-3-64.

*Geraldine Hays*  
 Geraldine Hays, Notary Public