

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED December 16, 1965  
STATE CORPORATION COMMISSION

DEC 28 1965  
12-28-1965  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Kenneth Smith of Flint Eng. & Constr. Co. has this date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: W. R. Allam

Complete Address: P.O. Box 92, Haven, Kansas

Lease Name: Mueller Well No. 1

Location: C NW NE Sec. 30 Twp. 24 Rge. 4 (E) (W) X

County Reno Total Depth 3698' Oil Well       

Gas Well        Input Well        SWD Well        D & A X Lost Hole       

Mr. Smith was instructed to plug the well as follows:

Fill hole with sand to 2970' and cement with 3 sacks.

Fill hole with mud to 310'. Set rock bridge from 310' to

300' and cement hole with 30 sacks. Fill hole with mud to

35'. Set rock bridge from 35' to 25' and cap hole with 15

sacks cement.

Very truly yours,

Conservation Division Agent